

IWQ 15-11 Pavement Patching

SCOPE OF WORK

2015 Patching:

The contractor shall furnish all materials, equipment, and labor to complete the required construction as described in its entirety to the specifications as directed and the terms of this contract including all incidentals as directed by the City of Dunwoody Director of Public Works or his representative. Unless otherwise specified all work shall be completed in accordance with Georgia Department of Transportation Standard Specifications (current edition).

Seeking per ton cost. Cost shall account for all ancillary costs to include mobilization, milling, traffic control, and material. Bid does not require bonding.

The work locations and descriptions follow but are not limited to:

- **Springfield Drive (689 SY)** Marked locations. Variable depth edge mill asphalt pavement, Overlay with 12.5mm @ 275lbs/sy.
- **Vernon Ridge Drive (58 SY)** Marked location. Variable depth edge mill asphalt pavement, Overlay with 12.5mm @ 275lbs/sy.
- **Vernon Ridge Court (8 SY)** Marked location. Variable depth edge mill asphalt pavement, Overlay with 12.5mm @ 275lbs/sy.
- **Mount Vernon Way (135 SY)** Marked locations. Variable depth edge mill asphalt pavement, Overlay with 12.5mm @ 275lbs/sy.

Proposals are due by 2:00 pm, on Wednesday, December 16, 2015.

* Prices are expected to be confirmed for a period of **120 days** to allow for weather and/or scheduling requirements.