

IWQ 15-11 Pavement Patching

SCOPE OF WORK

2015 Patching: The contractor shall furnish all materials, equipment, and labor to complete the required construction as described in its entirety to the specifications as directed and the terms of this contract including all incidentals as directed by the City of Dunwoody Director of Public Works or his representative. Unless otherwise specified all work shall be completed in accordance with Georgia Department of Transportation Standard Specifications (current edition). The work locations and descriptions follow but are not limited to:

- **Springfield Drive (689 SY)** Marked locations. Variable depth mill asphalt pavement, Overlay with 9.5 mm Superpave @ 330 lbs/sy.
- **Vernon Ridge Drive (58 SY)** Marked location. Variable depth edge mill asphalt pavement, Overlay with 9.5 mm Superpave @ 330 lbs/sy.
- **Vernon Ridge Court (8 SY)** Marked location. Variable depth edge mill asphalt pavement, Overlay with 9.5 mm Superpave @ 330lbs/sy.
- **Mount Vernon Way (135 SY)** Marked locations. Variable depth edge mill asphalt pavement, Overlay with 9.5 mm Superpave @ 330lbs/sy.

Proposals are due by 2:00 pm, on Wednesday, December 16, 2015.

*** Prices are expected to be confirmed for a period of 120 days to allow for weather and/or scheduling requirements.**