

November 17, 2014

RFP 14-16 Signal, Sign and Streetlight Maintenance

ADDENDUM 1

### Questions and Answers

1. We did not see a Cost Proposal Form in the RFP. How can we obtain that? A cost proposal form has been posted under the bid advertisement on the city's website. A paper and Excel file of the bid form should be submitted.

2. Is a General Contractor's license mandatory in order to bid this project?

A General Contractor's license is not required if the contractor or subcontractors are qualified by the GDOT in the work areas specified in the scope of services.

3. One of the minimum qualifications is a Level 1 Sign and Pavement Marking Technician. In lieu of this, would a subcontractor prequalified by GDOT in any of the following work codes satisfy this qualification? Highway Signs, Painting Traffic Stripe, Preformed Plastic Marking, Thermoplastic Traffic Stripe.

Yes provided that the contractor or subcontractor is qualified in all of these work codes.

4. Is the City's expectation that the contractor submits one monthly lump sum price to cover all emergency response, task order and routine maintenance services?

The monthly lump sum in the cost proposal form is intended to cover all labor and equipment (i.e. bucket truck, tools, etc.) costs for all task orders, routine maintenance and sign replacement. In addition to the task orders, the city expects to replace about 500 signs per year on a neighborhood by neighborhood basis. Emergency response will be billed on an hourly basis as needed.

5. Under working hours, it appears the City is requesting the contractor to maintain dedicated staffing for an established 8-hour period to conduct City-only business. Is that correct? If so, are the staffing levels at the contractor's discretion so as to meet the response times set forth?

The contractor shall provide the required staffing level to meet the response times set forth. There are no minimum hours.

6. What is the anticipated annual spend amount for all services, material, etc. rendered under this contract?

City has budgeted \$200,000.00 for signal maintenance in 2015 and has additional funds set aside to fund sign replacement materials.

7. Can you please provide a plan holders list?

There are no plan holders

**Bid form for RFP 14-16: Please submit the electronic excel file. Electronic Excel file posted on the city's website under RFP 14-16**

WorkOrderId	Date Initiated	Description	Priority	Instructions
140508001	5/8/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Locate and mark signal fiber for intersections at Ashford Dunwoody Rd and MeadowLane as well as Ashford Dunwoody Rd at Ashford Parkway. Contact for Cable East is Mike Blaylock 404-993-7414
140508006	5/8/14	BULB REPLACEMENT	3	Replace NB green bulb on Ashford Dunwoody Rd at Meadowlane Drive
140509005	5/9/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Replace Phase 3, side street left turn loop
140528004	5/28/14	CHECK TIMING	2	Check timing/check loops on Manhasset/Vermack Rd at Mt Vernon Road and at Mt Vernon Way at Mt Vernon Road. Problem was noted on the weekends as extended wait times for side roads.
140617009	6/17/14	BULB REPLACEMENT	2	Red bulb out at EB Cotillion at N Peachtree Rd.
140617010	6/17/14	BULB REPLACEMENT	2	Replace green bulb for NB North Shallowford Rd at Savoy
140617011	6/17/14	BULB REPLACEMENT	2	Replace red bulb on Meadow Lane EB at Ashford Dunwoody Rd.
140617028	6/17/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	4	Clean, repair and provide pest and weed control to signal cabinet at N Peachtree Rd and Cotillion Drive
140617029	6/17/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	4	Provide cleaning, repair, pest and weed control to signal cabinet at N Peachtree Rd and Dunwoody Crossing.
140617030	6/17/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	4	Provide cleaning, repair, pest and weed control to signal cabinet located on N Peachtree Rd at Kings Point Drive.
140618001	6/18/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Add northbound right turn loop, westbound left turn loop and eastbound setback loop.
140619001	6/19/14	RESET LIGHT FROM FLASH	1	Signal at N Peachtree and Savoy in flash.
140620001	6/20/14	RESET LIGHT FROM FLASH	1	Reset lights in flash at Dunwoody Club Drive and Winters Chapel Rd
140623001	6/23/14	RESET LIGHT FROM FLASH	1	Lights in flash at Mt Vernon at Dunwoody Club Dr, Jet Ferry Rd, and Tilly Mill Rd
140624001	6/24/14	BULB REPLACEMENT	2	Replace Red Bulb at N Peachtree and EB on ramp to 285
140630002	6/30/14	BULB REPLACEMENT	2	Replace Red LED
140630003	6/30/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	
140630004	6/30/14	RESET LIGHT FROM FLASH	1	Reset Light
140630005	6/30/14	RESET LIGHT FROM FLASH	1	Reset Light
140630006	6/30/14	RESET LIGHT FROM FLASH	1	Reset Light
140704001	7/4/14	RESET LIGHT FROM FLASH	1	Reset Light
140704002	7/4/14	RESET LIGHT FROM FLASH	1	Reset Light
140709001	7/9/14	RESET LIGHT FROM FLASH	1	Reset signal in flash at Savoy Dr and N Peachtree Rd.
140709009	7/9/14	BULB REPLACEMENT	2	Replace red bulb at signal for Savoy Dr and N Peachtree Rd.
140714004	7/14/14	RESET LIGHT FROM FLASH	1	Reset light from flash at Savoy and N Peachtree
140715002	7/15/14	RESET LIGHT FROM FLASH	1	Reset light from flash at Savoy Dr and N Peachtree Rd. Reported out at 7:30AM on 7/15/14
140723005	7/24/14	RESET LIGHT FROM FLASH	1	Reset light from flash at N Peachtree Rd and Tilly Mill Rd
140723006	7/24/14	RESET LIGHT FROM FLASH	1	Reset light from flash at Tilly Mill Rd and Peeler Rd
140723021	7/30/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace Camera Assembly
140723022	7/30/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace green LED
140723023	7/30/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace ADA push button

140723024	7/30/14	BULB REPLACEMENT	2	Replace Red LED
140723025	7/30/14	RESET LIGHT FROM FLASH	1	Replace cabinet controller
140723027	8/1/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	1	Signal stuck on red in all directions. Reported at 10:17AM
140723028	8/1/14	RESET LIGHT FROM FLASH	1	Signal reported out at Dunwoody Club Drive and Winters Chapel Rd.
140723029	8/4/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Low hanging loose signal wire may need to be removed if below 15' at the corner of Dunwoody Club Drive and Mt Vernon Rd.
140723032	8/8/14	CHECK TIMING	2	Check school flasher clocks and turn on flashers
140723033	8/8/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	1	Replace broken signal head
140723050	8/11/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Secure low hanging signal wires
140723051	8/11/14	BULB REPLACEMENT	2	Replace yellow bulbs in school flasher
140723060	8/15/14	BULB REPLACEMENT	2	Replace red signal bulb at Northbound Tilly Mill Rd @ Mount Vernon Rd, the right-side red bulb is out.
140723061	8/15/14	FIX LOOP	2	Check Phase 1 loop for constant call. Located at Womack Rd
140827002	8/27/14	BULB REPLACEMENT	2	Replace WB right side red bulb at Perimeter Center East and Ashford Dunwoody Rd.
140828001	8/28/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace clock on school flasher
140828002	8/28/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace clock on school flasher
140829004	8/29/14	FIX LOOP	2	Redraw detection zones for signal
140829006	8/29/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Install pedestrian signals as shown on provided plan
140901002	9/1/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Turn on all school flashers and adjust time
140902001	9/2/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Cabinet maintenance
140902002	9/2/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Cabinet maintenance
140902003	9/2/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Cabinet maintenance
140902004	9/2/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Cabinet maintenance
140905005	9/5/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Repair 2 bad loops
140905014	9/5/14	RESET LIGHT FROM FLASH	1	Pedestrian pole hit and light in flash.
140905016	9/5/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Install new pedestrian pole
140908005	9/8/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	1	Repair pedestrian push button phase 4 westbound
140910001	9/10/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Repair Phase 1 loop
140917001	9/17/14	BULB REPLACEMENT	2	Replace left side red bulb facing Spalding Club Court
140917002	9/17/14	RESET LIGHT FROM FLASH	1	Reset light from flash at Ashford Dunwoody Rd and Ravinia North
140917013	9/17/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace fallen pedestrian signal located at intersection of N Peachtree Rd and Savoy Drive
140922003	9/22/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	
140922012	9/23/14	BULB REPLACEMENT	2	Replace the left side green bulb for EB Spalding at Chamblee Dunwoody Rd.
140922015	9/23/14	BULB REPLACEMENT	2	Replace red bulb facing Tilly Mill Rd
140922017	9/23/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Install pedestrian signals per plan at Winters Chapel and Peeler Rd.
140922018	9/23/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Install striping for pedestrian crosswalks at Winters Chapel and Peeler Rd per plan detail
140922019	9/24/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Ped push button appears not to be working on School side of crosswalk. May require repair/replacement

140922034	9/30/14	CHECK TIMING	2	Caller claims that the signal at Mount Vernon Rd and Mount Vernon Way is suddenly favoring Mount Vernon Way such that more traffic is backing up on Mount Vernon Road than was previously occurring.
140922035	10/1/14	CHECK TIMING	2	Repair phase 4 splices
140922036	10/1/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Locate signal wiring for contractor
140922038	10/1/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace ped button
140922039	10/1/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Replace ped pole at location
140922041	10/1/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Fix signal for Austin Elementary Ped Crossing.
140922062	10/13/14	RESET LIGHT FROM FLASH	1	Reset light from flash at Winters Chapel and Peeler Rd.
140922086	10/16/14	BULB REPLACEMENT	2	Replace red bulb westbound on Perimeter Center East WB at Ashford Dunwoody Rd intersection.
140922087	10/16/14	BULB REPLACEMENT	2	Replace red bulb at Ashford Dunwoody Rd NB at intersection with Perimeter Center East
140922097	10/16/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	2	Southeastern signal pole at the intersection of Ashford Dunwoody Rd and Ashford Center Parkway has exposed signal wiring. Needs to be recessed inside of the pole and covered.
141020002	10/20/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	
141020003	10/20/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Repaired bad push button on NE corner of the intersection
141021003	10/21/14	BULB REPLACEMENT	2	Replace green bulb at signal WB on Meadow Lane Rd and Ridgeview Rd.
141027002	10/27/14	REPAIR/REPLACE/REMOVE SIGNAL ITEM	3	Remove span wire located at the NE corner of Peachford Rd and N Shallowford Rd to allow utilities to be removed from orphan pole.
141031001	10/31/14	BULB REPLACEMENT	1	Replace pedestrian signal bulb at NE corner of Tilly Mill and N Peachtree Rd.

WorkOrderId	Date Initiated	Description	Priority	Instructions
140501003	5/1/14	SIGN REPLACEMENT	2	Replace bent post for street name blades at the corner of Corners Drive and Mt Vernon Rd.
140501010	5/1/14	SIGN REPLACEMENT	2	Replace broken sign on the ground at the crosswalk at Stratham on Mt Vernon Rd.
140501011	5/1/14	INSTALL NEW SIGN	3	Install STOP sign and 2 street name blades on post. Street names are Ridgeview Rd and Manoah Ct.
140501012	5/1/14	SIGN REPLACEMENT	2	Install Street Name Blade for BETHESDA CT as well as a NO OUTLET topper.
140508002	5/8/14	SIGN REPAIR	2	Median sign bent at post on south median of Ashford Dunwoody Rd and Meadow Lane Rd. Replace post. R4-7 sign post
140509004	5/9/14	SIGN REPAIR	4	Refresh existing crosswalk with standard GDOT crosswalk (longitudinal bars)
140512002	5/12/14	INSTALL NEW SIGN	3	Replace SNS for this location
140512004	5/12/14	INSTALL NEW SIGN	4	Install Speed Limit sign on SB Ridgeview Rd north of Meadow Lane
140512005	5/12/14	SIGN REPLACEMENT	2	Replace bent post for street name blades at the corner of Corners Drive and Mt Vernon Rd.
140512006	5/12/14	INSTALL NEW SIGN	4	Install R10-7 sign indicating "Do not block intersection" on N Shallowford Rd just south of intersection with Village Drive. Additional work order for adjacent stop bar will be created
140513001	5/13/14	INSTALL NEW SIGN	1	Replace MUTCD R2-1 Yield sign and post that has been run over by a tractor trailer.
140519002	5/19/14	SIGN REPLACEMENT	3	Replace stop sign and street name blades. NOTE: BRING OLD SIGNS TO CITY HALL.
140527001	5/27/14	INSTALL NEW SIGN	1	Replace MUTCD R2-1 Yield sign and post that has been run over by a tractor trailer.
140527002	5/27/14	SIGN REPAIR	3	
140530005	5/30/14	INSTALL NEW SIGN	4	Install crosswalk striping across E Kings Point Circle at n Peachtree Rd.
140530006	5/30/14	SIGN REPLACEMENT	3	Replace old "City Limit" sign onto existing post at SB Roberts Drive south of Spalding Drive
140613001	6/13/14	INSTALL NEW SIGN	1	
140613002	6/13/14	SIGN REPLACEMENT	3	Install "SCBDD" sign at Mt Vernon Rd EB after COD sign on Mt Vernon prior to Ridgeview Rd
140613003	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign at Spalding Drive NB north of Dunwoody Rd
140613004	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign at Jett Ferry Rd SB south of Dunwoody Club Drive
140613005	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign at N Peachtree Rd NB prior to E Kings Point Circle and prior to SCBDD and R2-1 Speed Limit signs
140613006	6/13/14	INSTALL NEW SIGN	3	Install "SCBDD" sign at Hunters Branch Drive EB to Hidden Branches Dr on sharing pole with COD sign
140613007	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign at Hunters Branch Drive EB to Hidden Branches Dr after COD sign
140613008	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign at Jett Ferry Rd SB south of Dunwoody Club Drive
140613009	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign along Hunters Branch Ln EB to Winding Branch Cir
140613010	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign along Hunters Branch Ln EB to Winding Branch Cir after COD sign
140613011	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign on EB Dunwoody Rd east of Spalding Drive
140613012	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign on EB Dunwoody Rd east of Spalding Drive
140613013	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign on EB Perimeter Center West prior to Crowne Point Pkwy

140613014	6/13/14	INSTALL NEW SIGN	3	Install "SCBDD" sign on EB Perimeter Center West prior to Crowne Point Pkwy
140613015	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign on EB Perimeter Center West prior to Crowne Point Pkwy
140613016	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign on EB Central Pkwy prior to Perimeter Center West after COD and SCBDD signs
140613017	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign at Hammond Drive EB prior to Perimeter Center Parkway after COD and SCBDD sign
140613019	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign at N Shallowford Rd NB prior to Peachford Rd and prior to SCBDD and R2-1 Speed Limit signs
140613020	6/13/14	SIGN REPLACEMENT	1	Stop sign is down at Mt Vernon Rd and Meadowlake needs to be repaired.
140613021	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign at Hammond Drive EB prior to Perimeter Center Parkway
140613022	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign on Perimeter Center Pkwy NB prior to Hammond Drive.
140613023	6/13/14	INSTALL NEW SIGN	3	Install "SCBDD" sign on Perimeter Center Pkwy NB prior to Hammond Drive after COD sign
140613024	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign on Perimeter Center Pkwy NB prior to Hammond Drive after COD sign
140613025	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign at Ashford Dunwoody Rd NB prior to Ravinia Parkway
140613026	6/13/14	INSTALL NEW SIGN	3	Install "R2-1 Speed Limit" sign at Chamblee Dunwoody Rd prior to Dunwoody Park after COD and SCBDD signs
140613027	6/13/14	INSTALL NEW SIGN	3	Pick up 2 Rotary Club Meeting signs from Public Works (from Mindy); Install signs on two existing Rotary Club signs on Ashford-Dunwoody:1) Southbound side - Just north of Hammond.2) Northbound side - Just south of Hammond.
140613028	6/13/14	INSTALL NEW SIGN	3	Install new R7-2a sign on westbound side of Brookhurst just west of Dunhaven Road with hours from 7 a.m. to 3 p.m. and M-F placard and To Corner placard with arrow pointing towards North Peachtree Road
140613029	6/13/14	INSTALL NEW SIGN	3	Install Next Signal placard below Chamblee Dunwoody Road guide sign.
140613030	6/13/14	SIGN REPLACEMENT	1	Replace Stop Sign, post, street name blades for Cedarhurst Dr and Womack Rd.
140613031	6/13/14	SIGN REPLACEMENT	3	Replace R1-1 Stop Sign due to extreme fading.
140613032	6/13/14	SIGN REPLACEMENT	3	Replace faded R1-1 Stop sign at the corner of Wickenby Ct and Womack Rd
140613033	6/13/14	INSTALL NEW SIGN	3	
140613034	6/13/14	SIGN REPLACEMENT	3	
140613035	6/13/14	SIGN REPLACEMENT	3	Replace overhead R10-11a with R10-11. Evaluate moving the sign to the right instead of between the two signals to improve visibility.
140613042	6/13/14	SIGN REPLACEMENT	3	Replace yield and street name signs
140613043	6/13/14	INSTALL NEW SIGN	3	Install ' Dunwoody City Limits' sign SB Peachtree Industrial Blvd south of Winter's Chapel Rd
140613044	6/13/14	INSTALL NEW SIGN	3	Install "City of Dunwoody" sign at Hunters Branch Drive EB to Hidden Branches Dr
140613045	6/13/14	INSTALL NEW SIGN	3	Remove 10 signs along Saffron Drive. 8 located at speed humps. 2 'Warning' signs located at start of Saffron Drive on either end. Replace with 'Speed Hump Ahead' signs at either end of Saffron to warn of upcoming speed humps. (See Attached image)

140613046	6/13/14	INSTALL NEW SIGN	4	Install new W11-9 sign in fluorescent yellow with W16-5P plaque pointing to pedestrian crossing at Barclay. Also add a supplemental plaque with the words Visually Impaired
140613047	6/13/14	INSTALL NEW SIGN	3	Install R7-2A eastbound on Brookhurst near corner of North Peachtree with hours of 7 a.m. to 3 p.m. and M-F placard and To Corner Placard with arrow pointing towards Dunhaven Road.
140613048	6/13/14	INSTALL NEW SIGN	3	Install 'No Left Turn (7am-9am) on west side of Tilly Mill Rd just south of Dunkerrin Lane to match existing sign on east side of Tilly Mill Rd.
140613049	6/13/14	INSTALL NEW SIGN	4	Move Eastbound Deer Crossing W11-3 Sign from 4787 Dunwoody Club Drive west to 4661 Dunwoody Club Drive so it will be West of the Creek for drivers.
140613050	6/13/14	INSTALL NEW SIGN	3	Add 2 No Parking Signs with two way arrow between existing No Parking signs on the west side of Dunwoody Park North. One sign should go midway between Dunwoody Park and the bank driveway. The other should be placed just north of the Jewish Family Services drive. Also add sign on south end of east side of Dunwoody Park about 30 feet from Dunwoody Park with back to corner placard.
140616001	6/16/14	INSTALL NEW SIGN	3	Install stop bar at the "Do not Block Intersection" sign on N Peachtree and Peeler Rd to limit traffic blocking access from Peeler Rd to N Peachtree Rd.
140617001	6/17/14	SIGN REPLACEMENT	4	Replace 2 stop signs at north exit for Dunwoody High School onto Vermack Rd.
140617007	6/17/14	SIGN REPAIR	2	Stand up "keep right" sign in median along Meadow Lane Drive while performing ROW maintenance cleanup.
140617013	6/17/14	INSTALL NEW SIGN	4	Paint centerline along Nandina Lane
140617014	6/17/14	SIGN REPAIR	2	Leaning median division sign traveling NB on Ashford Dunwoody Rd just north of Ashford Center Parkway.
140617022	6/17/14	SIGN REPAIR	2	Stop sign is leaning at Withmere Close and Mt Vernon Way. Post seems to be intact.
140617024	6/17/14	INSTALL NEW SIGN	2	Install 1 in street crosswalk sign and 4 crosswalk signs on 2 posts on either side of the new Georgetown Park crosswalk on Chamblee Dunwoody Rd.
140617025	6/17/14	SIGN REPLACEMENT	3	Remove DDI signs for PCID at Ashford Dunwoody Rd and I-285.
140617026	6/17/14	SIGN CLEANING	4	Clean 'One Way' sign located on Perimeter Center East on southside leaving City Hall and heading toward Ashford Dunwoody Rd.
140617033	6/17/14	SIGN REPAIR	2	Remove 2 signs for "Coming Soon Georgetown Park" along N Shallowford Rd and Chamblee Dunwoody Rd.
140618013	6/18/14	SIGN REPAIR	2	
140624002	6/24/14	INSTALL NEW SIGN	3	Install 3 stop bars at the intersection of Fontainebleau Dr and Fontainebleau Way
140624003	6/24/14	INSTALL NEW SIGN	3	Mark Speed pavement indicating speed hump
140624004	6/24/14	INSTALL NEW SIGN	3	Update Crosswalk (Thermo) at Vermack Rd and Parliament Dr
140624005	6/24/14	SIGN REPLACEMENT	3	Replace missing Dunwoody Road street name sign.
140624006	6/24/14	INSTALL NEW SIGN	3	Install R10-7 sign on N Peachtree Rd indicating not to block intersection of Peeler Rd and N Peachtree Rd. Separate work order in place for adding stop bar alongside sign indicating stop area along N peachtree Rd.
140624007	6/24/14	SIGN REPLACEMENT	3	Replace old "City Limit" sign onto existing post at SB Roberts Drive south of Spalding Drive
140624008	6/24/14	SIGN REPLACEMENT	4	Replace 2 stop signs at north exit for Dunwoody High School onto Vermack Rd.
140624009	6/24/14	SIGN REPLACEMENT	3	Remove DDI signs for PCID at Ashford Dunwoody Rd and I-285.

140630008	6/30/14	INSTALL NEW SIGN	3	Install No Parking signs on Riverglenn Cir between North Peachtree Road and Ellsbury Drive as follows:
140709005	7/9/14	SIGN REPLACEMENT	2	Replace 2 "stop here on red signs" : 1 located on westbound exit ramp at 285 and Ashford Dunwoody Rd, 1 located on overhead mast arm near signal heads.
140709006	7/9/14	INSTALL NEW SIGN	3	Replace faded "Yield" sign located on Wilder Ct at Vernon Lake Drive
140709008	7/9/14	SIGN REPAIR	2	Reset " Yield" sign leaning at location
140710008	7/10/14	INSTALL NEW SIGN	3	Add "Bike Lane" signs (R3-17) on Peachford Road EB and WB directions. Will provide a location map.
140711001	7/11/14	INSTALL NEW SIGN	4	Paint centerline along Nandina Lane
140714001	7/14/14	INSTALL NEW SIGN	4	Install an additional R10-12 on the mast arm on the south side of the intersection for Ashford Dunwoody Road to supplement the one on the north side.
140714005	7/14/14	INSTALL NEW SIGN	3	Replace faded "Yield" sign located on Wilder Ct at Vernon Lake Drive
140714008	7/14/14	INSTALL NEW SIGN	4	Continue centerline with skip striping (Thermo) from Tilly Mill Rd South of intersection to Mt Vernon Place centerline. Drawing attached.
140714009	7/14/14	INSTALL NEW SIGN	3	Stripe a skipped yellow centerline following Spalding Road, filling in the existing gap across the intersection.
140714010	7/14/14	INSTALL NEW SIGN	4	Install crosswalk striping across E Kings Point Circle at n Peachtree Rd.
140714011	7/14/14	INSTALL NEW SIGN	2	Install 1 in street crosswalk sign and 4 crosswalk signs on 2 posts on either side of the new Georgetown Park crosswalk on Chamblee Dunwoody Rd.
140714017	7/14/14	SIGN REPAIR	2	Replace twisted pole and stop sign at location.
140716001	7/16/14	INSTALL NEW SIGN	3	Add "No U Turn" sign to center median at Ashford Dunwoody Rd and Hammond Drive for NB Ashford Dunwoody drivers.
140716002	7/16/14	INSTALL NEW SIGN	3	Repaint center median small concrete island located on Ashford Dunwoody Rd just north of intersection to Hammond Drive to increase visibility.
140716003	7/16/14	SIGN REPLACEMENT	3	Replace 2 SB facing faded "No Parking" signs located at the corner of Parliament Drive and Parliament Way and south one property.
140716007	7/16/14	INSTALL NEW SIGN	3	Install W9-1 w/ W16-2 and W9-2 signs to the north side of Mt Vernon Road as shown on Sprinkle plan. This plan will be emailed separately. Remove any existing signs that conflict with these new signs. (Right Lane Merge Ahead w/ W16-2 and W4-2)
140723004	7/24/14	SIGN REPLACEMENT	2	Replace SNS with corrected spelling "Laurelwood Rd" at Tilly Mill Rd.
140723039	8/11/14	SIGN REPLACEMENT	3	Refresh crosswalk striping
140723042	8/11/14	INSTALL NEW SIGN	3	Add 2 crosswalk signs at the crosswalk location
140723044	8/11/14	SIGN REPLACEMENT	3	Refresh crosswalk striping on south side of intersection
140723046	8/11/14	INSTALL NEW SIGN	3	Install W11-2 with Ahead placard on the east side of Tilly Mill Road on the north side of the south driveway for Congregation Ariel.
140723047	8/11/14	INSTALL NEW SIGN	3	Add W11-2 sign with Ahead placard on west side of road, south of Dartford Drive.
140723048	8/11/14	SIGN REPAIR	3	Refresh crosswalk on south side of intersection.
140820001	8/20/14	SIGN REPAIR	3	Stop sign is leaning
140821001	8/21/14	SIGN REPAIR	2	Reset sign that has been hit and is leaning.
140828003	8/28/14	INSTALL NEW SIGN	3	Install Public Meeting signs along Mt Vernon Rd
140828005	8/28/14	SIGN REPLACEMENT	3	Replace Street Name Blade with 'No Outlet' on side of no outlet or leave 'No Outlet' off of street name blade and add separate 'No Outlet' sign
140829001	8/29/14	SIGN REPLACEMENT	3	Refresh crosswalk striping on south side of intersection

140829002	8/29/14	SIGN REPLACEMENT	3	Refresh crosswalk striping
140829003	8/29/14	INSTALL NEW SIGN	4	Add bike lane obstruction white line (Thermo) around cut out in gutter at 5343 Roberts Drive. 30' taper.
140905006	9/5/14	INSTALL NEW SIGN	4	Add two new Meadow Lane Road illuminated signs with arrow pointing east on the north and south side of the intersection. Adjust the Crown Pointe Parkway sign on the south side of the intersection as necessary.
140905007	9/5/14	SIGN REPLACEMENT	3	Install new street name blades. Stop sign was replaced but street name blades are missing.
140909013	9/9/14	SIGN REPAIR	2	Remove 1 fallen and 1 standing "one way" road sign in medians at Meadow Lane just south of Perimeter Center North. Replace with 2 R4-7 divided road signs
140909014	9/9/14	SIGN REPAIR	2	Re-install "Yield to Bike Lane" sign located just west of Ashford Dunwoody Rd on north side of Meadow Lane Rd
140909015	9/9/14	SIGN REPLACEMENT	4	Replace overhead lighted sign faces for Meadow Lane Rd at Ashford Dunwoody Rd. Signs currently read "Meadow Lane". Need to read "Meadow Lane Rd"
140909017	9/9/14	SIGN REPLACEMENT	3	Remove overhead lane assignment sign and replace with side mount
140915001	9/15/14	INSTALL NEW SIGN	2	Install "End School Zone" sign on Roberts Drive north of Austin Elementary School.
140918007	9/18/14	SIGN REPAIR	2	Remove "Do Not Enter" Sign located in median of Ashford Dunwoody Rd just north of Valley View Rd.
140922002	9/22/14	INSTALL NEW SIGN	2	Install temporary striping or signage to the speed humps located on Cherring Lane due to recent repaving.
140922005	9/23/14	INSTALL NEW SIGN	3	Add "No U Turn" sign to center median at Ashford Dunwoody Rd and Hammond Drive for NB Ashford Dunwoody drivers.
140922006	9/23/14	INSTALL NEW SIGN	3	Install W11-2 with Ahead placard on the east side of Tilly Mill Road on the north side of the south driveway for Congregation Ariel.
140922007	9/23/14	INSTALL NEW SIGN	3	Add "Bike Lane" signs (R3-17) on Peachford Road EB and WB directions. Will provide a location map.
140922008	9/23/14	INSTALL NEW SIGN	3	Add W11-2 sign with Ahead placard on west side of road, south of Dartford Drive.
140922013	9/23/14	SIGN REPLACEMENT	2	Replace SNS with corrected spelling "Laurelwood Rd" at Tilly Mill Rd.
140922029	9/29/14	INSTALL NEW SIGN	3	Install stop sign and street name blades at entrance to new subdivision Street names: Mount Vernon Place, Falkirk Drive
140922037	10/1/14	INSTALL NEW SIGN	2	Install temporary striping or signage to the speed humps located on Cherring Lane due to recent repaving.
140922045	10/6/14	SIGN REPLACEMENT	2	Replace Stop Sign located at Village Springs Run facing Devonshire Rd
140922046	10/6/14	SIGN REPLACEMENT	3	Replace 2 overhead directional signs on Chamblee Dunwoody Rd NB just south of Old Springhouse Lane. 1 sign indicates left turn arrow for lane and 1 sign indicates straight arrow for lane
140922047	10/6/14	SIGN REPLACEMENT	2	Repair leaning speed limit sign at NB Winters Chapel Rd just north of Peeler Rd.
140922048	10/6/14	SIGN REPAIR	2	Replace bulb for overhead illuminated street name sign for Ashford Dunwoody Rd at Perimeter Center North
140922049	10/6/14	SIGN REPAIR	4	Remove DeKaib Police Neighborhood Watch and No Soliciting sign from No Outlet sign located on Old Springhouse Lane WB
140922050	10/7/14	INSTALL NEW SIGN	3	Install R10-15 overhead sign facing Womack at Chamblee Dunwoody.
140922051	10/7/14	SIGN REPAIR	2	Correct leaning speed limit sign located at 4537 Chamblee Dunwoody Rd.

140922052	10/7/14	SIGN REPAIR	3	Install Caution Left Arrow at sharp turn on Leisure Drive. Pole is in place but sign is missing
140922055	10/7/14	SIGN REPLACEMENT	3	Replace faded Dunwoody city limit sign with new green background with white letters: Dunwoody City Limits
140922063	10/13/14	SIGN REPLACEMENT	4	Replace signs
140922064	10/13/14	INSTALL NEW SIGN	3	Add overhead street name signs. Roberts Drive on east span wire. Chamblee Dunwoody Road on the north and south span wire at the intersection.
140922065	10/13/14	INSTALL NEW SIGN	3	Add yellow hatching (Thermo) in median north of Georgia Power entrance at 4404 N Shallowford Rd.
140922066	10/13/14	INSTALL NEW SIGN	4	Add stop bars (Themo) at all three legs of Fontainebleau Dr and Joel Ln.
140922067	10/13/14	INSTALL NEW SIGN	4	Add stop bars (Thermo) at all three legs of Fontainebleau Dr and Fleur de Lis Place
140922068	10/13/14	INSTALL NEW SIGN	4	Refresh crosswalk markings (paint) at Ashford Dunwoody Rd and Perimeter Center East
140922069	10/13/14	SIGN REPLACEMENT	4	Replace Faded Stop Sign on Southwest corner of Fontainebleau Dr and Happy Hollow Rd
140922070	10/13/14	SIGN REPLACEMENT	2	Replace broken sign in pedestrian crossing at Dunwoody Elementary. Broken as of Friday 1/17/14 2:30PM
140922071	10/13/14	INSTALL NEW SIGN	3	Install NO TRESPASSING signs at Brook Run Theatre and Dorms for enforcement.
140922072	10/13/14	INSTALL NEW SIGN	3	Install "End School Zone" EB from Womack Rd on Speed Limit Sign east of Dunwoody Elementary
140922073	10/13/14	INSTALL NEW SIGN	3	Install 3 stop bars at the intersection of Fontainebleau Dr and Fontainebleau Way
140922074	10/14/14	INSTALL NEW SIGN	3	Add 2 crosswalk signs at the crosswalk location
140922075	10/14/14	SIGN REPLACEMENT	3	Replace faded Dunwoody city limit sign with new green background with white letters: Dunwoody City Limits
140922076	10/14/14	SIGN REPLACEMENT	2	Repair leaning speed limit sign at NB Winters Chapel Rd just north of Peeler Rd.
140922077	10/14/14	SIGN REPLACEMENT	2	Replace 2 "stop here on red signs" : 1 located on westbound exit ramp at 285 and Ashford Dunwoody Rd, 1 located on overhead mast arm near signal heads.
140922078	10/14/14	SIGN REPLACEMENT	2	Replace Stop Sign located at Village Springs Run facing Devonshire Rd
140922079	10/14/14	INSTALL NEW SIGN	3	Repaint center median small concrete island located on Ashford Dunwoody Rd just north of intersection to Hammond Drive to increase visibility.
140922080	10/14/14	SIGN REPLACEMENT	3	Install new street name blades. Stop sign was replaced but street name blades are missing.
141017001	10/17/14	INSTALL NEW SIGN	3	Install new 35 mph Speed Limit sign westbound on Hammond near Ashford Dunwoody
141020004	10/20/14	INSTALL NEW SIGN	3	Install stop sign and street name blades at entrance to new subdivision Street names: Mount Vernon Place, Falkirk Drive
141020005	10/20/14	SIGN REPLACEMENT	3	Replace 2 SB facing faded "No Parking" signs located at the corner of Parliament Drive and Parliament Way and south one property.
141021004	10/21/14	SIGN REPAIR	3	Remove DeKalb Police sign and pole at entrance to Village Mill Subdivision
141021006	10/21/14	SIGN REPAIR	3	Remove DeKalb Police sign located at the entrance to Witham Drive at Roberts Drive.
141021009	10/21/14	INSTALL NEW SIGN	3	Install 2 painted Right Turn Arrows in the southbound right turn lane on Chamblee Dunwoody at Redfield Road.
141021010	10/21/14	INSTALL NEW SIGN	3	Install thermo arrows on newly replaced speed hump on Devlerton.

141021011	10/21/14	INSTALL NEW SIGN	3	Install Bike Lane arrows along Mt Vernon Rd from Layfield Dr to Ashford Dunwoody Rd as required under previous parent work order.
141021013	10/21/14	INSTALL NEW SIGN	3	Install SCBDD and Speed Limit sign on singular pole along Mt Vernon Rd just east of Dunwoody City Limits sign.
141022001	10/22/14	SIGN REPLACEMENT	4	Replace 13 stop signs located in Chateau Woods subdivision to meet reflective requirements.
141029001	10/29/14	SIGN REPAIR	3	Replace backlight bulb for Crown Pointe Parkway mast arm illuminated sign facing south bound traffic
141102003	10/28/14	INSTALL NEW SIGN	3	Replace 13 stop signs located in Chateau Woods subdivision to meet reflective requirements.